

**DEPARTMENT OF TRANSPORTATION
STATE OF GEORGIA**


INTERDEPARTMENTAL CORRESPONDENCE

FILE

OFFICE Materials & Research
Forest Park, Georgia

DATE November 7, 2007

FROM

 Greg Mayo, P.E., Director of Construction

TO

Todd Long, P.E., Director of Preconstruction

SUBJECT New 9.5 mm Superpave Mixes Pay Item Descriptions

At the request of the Georgia Asphalt Pavement Association and in conjunction with the Office of Materials and Research and the Office of Contract Administration, four new pay items for 9.5 mm Superpave Mix have been created to alleviate confusion for Type and Group selection and pay items. The following table includes the new pay items and the ADT criteria for each:

Item No.	Description	Two-Way ADT
402-3100	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE I, GP 1 OR BLEND 1, INCL BITUM MATL & H LIME	Up to 800
402-3101	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE I, BLEND 1, INCL BITUM MATL & H LIME	≥800 to 2,000
402-3102	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, BLEND 1, INCL BITUM MATL & H LIME	≥2,000 to 4,000
402-3103	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II GP 2 ONLY, INCL BITUM MATL & H LIME	≥4,000 to 10,000


Use of these pay items will start with the January 2008 letting. A complete "Most Frequently Used Pay Items for 4.75 mm Mix and Superpave Mixes" pay items list is also included as an attachment and a ready reference for designers.

If you have any questions, please contact Georgene Geary at 404-363-7512, or David Hoge at (404) 656-5325.

Attachment

GM:GMG:PW:sh

cc: District Engineers, Randy Hart (Room 237); David Crim (TMC); Ben Buchan (Room 356); Brent Story (Room 444); Babs Abubakari (Room 433); David Huff (Room 201); Steve Matthews (Room 266)



Most Frequently Used Pay Items for 4.75 mm Mix and Superpave Mixes

Pay Item		Description	Two-Way ADT
402-3814	TN	RECYCLED ASPH CONC 4.75 MM MIX, GP1 OR 2, INCL BITUM MATL & H LIME	<800 and low truck volume
402-3816	TN	RECYCLED ASPH CONC 4.75 MM MIX, BLEND 1, INCL BITUM MATL & H LIME	< 1,000 and low truck volume
*402-3100	TN	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE I, GP 1 OR BLEND 1, INCL BITUM MATL & H LIME	<800
*402-3101	TN	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE I, BLEND 1, INCL BITUM MATL & H LIME	≥800 and < 2,000
*402-3102	TN	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, BLEND 1 INCL BITUM MATL & H LIME	≥2,000 and < 4,000
*402-3103	TN	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, GP 2 ONLY, INCL BITUM MATL & H LIME	≥4,000 and < 10,000
402-3130	TN	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	≥ 10,000 and <25,000
402-4510	TN	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	≥ 25,000 and < 50,000
402-3190	TN	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP1 OR 2, INCL BITUM MATL & H LIME	N/A – not a surface mix
402-3121	TN	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	N/A – not a surface mix

*First Use: January 2008 letting

For the complete pay items list, refer to “Pay Item Index” under “Bid Notices Reports” which is online at <http://www.dot.state.ga.us/dot/construction/contractsadm/>